BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to : **Original / Duplicate**

Name of the Work : Repairs and maintenance to existing borewells in Lottegollahalli, Devinagara, Muneshwaranagara, LKR nagara and Surroundings in ward no. 08, Kodigehalli.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	17	Lifting of Submersible pump set as per Soecification and direction etc complete as per specifications and directions of engineer in charge of the work	Each	850.00	Rupees Eight Hundred Fifty Only
2	17	Transportation of pumping machineries etc complete as per specifications and directions of engineer in charge of the work	Each	900.00	Rupees Nine Hundred Only
3	17	Labour charges (over hauling) etc complete as per specifications and directions of engineer in charge of the work	Job	550.00	Rupees Five Hundred Fifty Only
4	5	A) Repairs to Motor: Rewinding of submersible pump sets with copper insulation wire of suitable gauge as per ISI specification with guarantee of 6 months. **(Above 10 HP upto 20 HP add Rs.150/- for every ½ HP) up to 10 HP** etc complete as per specifications and directions of engineer in charge of the work		3700.00	Rupees Three Thousand Seven Hundred Only
4A	12	12.5 HP		4750.00	Rupees Four Thousand Seven Hundred Fifty Only
5	17	Starter (with one year Guarantee) etc complete as per specifications and directions of engineer in charge of the work	No.	5050.00	Rupees Five Thousand Fifty Only
6	17	Rotor (with one year Guarantee) etc complete as per specifications and directions of engineer in charge of the work	No.	4700.00	Rupees Four Thousand Seven Hundred Only
7	17	Upper Flange etc complete as per specifications and directions of engineer in charge of the work	No.	350.00	Rupees Three Hundred Fifty Only
8	17	Lower Housing etc complete as per specifications and directions of engineer in charge of the work	No.	650.00	Rupees Six Hundred Fifty Only
9	17	Carbon Housing etc complete as per specifications and directions of engineer in charge of the work	No.	475.00	Rupees Four Hundred Seventy Five Only
10	17	Thrust bearing block assembly complete with Segment bearing pad etc complete as per specifications and directions of engineer in charge of the work	No.	1150.00	Rupees One Thousand One Hundred Fifty Only
11	17	Oil Seal etc complete as per specifications and directions of engineer in charge of the work	No.	125.00	Rupees One Hundred Twenty Five Only
12	17	Oil Seal Steel Bush etc complete as per specifications and directions of engineer in charge of the work	No.	150.00	Rupees One Hundred Fifty Only
13	255	Guide vane etc complete as per specifications and directions of engineer in charge of the work	No.	175.00	Rupees One Hundred Seventy Five Only
14	255	Impeller Shell moulded with aluminium Bronze) etc complete as per specifications and directions of engineer in charge of the work	No.	425.00	Rupees Four Hundred Twenty Five Only
15	17	Discharge outlet (D.O) Bearing D.O Steel Bush etc complete as per specifications and directions of engineer in charge of the work	No.	445.00	Rupees Four Hundred Forty Five Only

ಕರಡು ಟೆಂಡರ್ ಷಡ್ಯೂಲ್‌ನ್ನು
ಶಿದ್ದುಪಡಿಗಳ ಸಂಖ್ಯೆ Nil)
ಶಿದ್ದುಪಡಿ ಮಾಡಿ/ಇಲ್ಲದೆ
ಅನುಮೋದನೆ ನೀಡಿಲಾಗಿದೆ

No & corrections - Nil

24/12

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ
ಬೃ.ಬೆ.ಮ.ಪಾ., ಬೆಂಗಳೂರು
24/12

No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
16	17	Steel Bush etc complete as per specifications and directions of engineer in charge of the work	No.	150.00	Rupees One Hundred Fifty Only
17	17	Pump shaft made out of stainless steel Centreless ground with key way (upto 8 stages) etc complete as per specifications and directions of engineer in charge of the work	No.	950.00	Rupees Nine Hundred Fifty Only
18	17	Non – return valve (NRV) assembly complete with rubber 'O' Ring etc complete as per specifications and directions of engineer in charge of the work	No.	1350.00	Rupees One Thousand Three Hundred Fifty Only
19	17	Cable Guard etc complete as per specifications and directions of engineer in charge of the work	No.	150.00	Rupees One Hundred Fifty Only
20	17	Brass Filter etc complete as per specifications and directions of engineer in charge of the work	No.	250.00	Rupees Two Hundred Fifty Only
21	17	Re-erection charges of pumping machineries including overhauling and pointing etc complete as per specifications and directions of engineer in charge of the work	Each	950.00	Rupees Nine Hundred Fifty Only
22	265.00	Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper conductor confirming to table 3 class 5 of IS:8130-1984 and virgin grade PVC insulation and sheathed suitable for working voltage upto 1100 Volts. P. No. 49/ I No. 29-b(1) **4 Sqm mm of 56 strands 0.3mm dia Group - A** etc complete as per specifications and directions of engineer in charge of the work	Mtr	151.00	Rupees One Hundred Fifty One Only

No of corrections - Nil.

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

Note:

1. Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)
2. Unit rates and prices shall be quoted by the Tender in Indian rupees.
3. Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)
4. Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

ಕರಡು ಟೆಂಡರ್ ಷರತ್ತುಗಳನ್ನು
ತಿದ್ದುಪಡಿಗಳ ಸಂಖ್ಯೆ Nil)
ತಿದ್ದುಪಡಿ ಮಾಡಿ/ಇಳಿಸಿ
ಅನುಮೋದನೆ ನೀಡಿಲಾಗಿದೆ

29.12.16